ENGINEERING DEPARTMENT.

KADUR DIVISION.

Dated 30th October 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 23rd November 1931, till 3 P.M., for improving Sree Anedevaragudi in Kalaseswaraswamy Temple at Kalasa. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalore between the hours of 11 A.M. and 5 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees eighty in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for improving Sree Anedevaragudi in Kalaseswaraswamy Temple at Kalasa, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rate should be quoted for each item of work.

10. Percentage rates below the lowest tender or estimated rates will not be accepted.

11. No claim for enhanced rates will be entertained after the acceptance of the tender or during the course of work.

Estimate for improving the Sree Anedevaragudi in Kalaseswaraswamy Temple at Kalasa.

	Items of work	Unit	Quantity	Sanctioned rate	Rates tendered	
					In figures	In words
				Rs. a. p.	Rs. a. p.	
1	Removing the existing wooden flooring in the upper story.	Sqr.	13·12	2 0 0		
2	Repairing the same and refixing 2/3 rectangular with fresh nails, etc.	„	12·08	6 0 0		
3	Providing new jungle wood planks in place of damaged ones and fixing the same.	C.ft.	6·14	0 8 0		
4	Providing and fixing jungle wood rafters in mathi in place of damaged ones during execution.	„	20	4 8 0		
5	Removing and repairing the ornamental wooden railings wherever necessary.	Lump	sum			
6	Providing and fixing wooden railings at the east and west end of southern extension.	S.ft.	32	1 8 0		
7	Chocolate painting to the above new railings and the old existing ones.	Sqr.	3·00	6 0 0		
8	Plastering with chunam mortar walls of front wings including patches here and there.	„	3·00	6 0 0		
9	Repairs to walls with brick masonry	Lump	sum			
10	Flooring with cuddapah slabs on 3" concrete and cement pointing.	Sqr.	14·96	50 0 0		
11	Removing and refixing slabs and lower verandah in front of side steps.	„	1·50	5 0 0		

	Items of work	Unit	Quantity	Sanctioned rate	Rates tendered	
					In figure	In words
				Rs. a. p.		
12	Providing an entrance to the first floor at the staircase :—					
	(a) Burnt brick in mud	C.ft.	197	0 5 0		
	(b) Plastering to the above here and there.	Sqr.	41·60	6 0 0		
	(c) Providing a teak wood door ...	S.ft.	23	3 0 0		
13	Providing teak-wood-props at the upper verandah in place of damaged ones.	C.ft.	17·50	8 0 0		
14	White-washing two coats ...	Sqr.	80·00	0 7 6		
15	Cement pointing with cement concrete patching to all crevices at straps in open yard here and there.	,,	15·00	6 8 0		
16	New tiles in place of damaged ones ...	No.	50	0 3 0		
17	Removing and refixing old ridge tiles set in mortar and cement pointing.	R.ft.	100	0 4 0		
18	New ridge for damaged ones ...	,,	30	1 0 0		
19	Unforeseen charges	Lump	sum			

L. A. H. WINCKLER,
Executive Engineer.

KOLAR DIVISION.

Abstract Notification, dated 8th October 1931.

The attention of the public is invited to the notification published in the *Mysore Gazette* Part VI, page 1156, dated 15th October 1931, calling for tenders for completing the remaining works for Restoring Gulichikkankunte of Hulaganahalli, Regd. No. 200 of Goribidnur Taluk, Kolar District.

Last date for tenders is 2 P.M., on 7th November 1931.

C. T. NARASIMHA IYENGAR,
Executive Engineer.

OFFICE OF THE EXECUTIVE ENGINEER, GAUGING AND UPPER CHANNELS DIVISION, MYSORE.

Notice dated 13th October 1931.

The Office of the Executive Engineer, Gauging and Upper Channels Division, Mysore, will be abolished from 1st November 1931 and will be amalgamated with the Dam Construction Division at Krishnarajasagara in pursuance of G. O. No. 543-50—K. S. S. 1652-59, dated 8th October 1931.

All communications intended for the Gauging and Upper Channels Division should be addressed to the Executive Engineer, Dam Construction Division, Krishnarajasagara from the 28th October 1931.

B. KRISHNA RAO,
Executive Engineer.

MEDICAL DEPARTMENT.

MATERNITY HOSPITAL, BANGALORE.

Abstract Notification.

Sealed tenders in triplicate for the supply of "Diet articles, etc.," required for the use of the inmates of the Maternity Hospital, Bangalore, during the Calendar year 1932, will be received by the undersigned on Monday the 23rd November 1931, at 11 A.M. For full details please see pages 1164 to 1166, Part VI, *Mysore Gazette*, dated 15th October 1931.

M. C. ALBUQUERQUE,
Medical Officer in charge.

6 c